

Ideas Provided by Factory Home Center



www.factoryhomecenter.com
888-521-7010

Block Crawlspace Package Estimates:

6 Course Foundation using 10" Block
20" x 10" Poured Footing using 2- ½" Re-Bar throughout
6 mil Ground Poly- material only(not installed)
Core Fill Every 4' with 1/2" Re-Bar & Water Proof Exterior Walls

Date: _____

*Estimate is good for 7 days

Size: _____

Estimate: _____

Insulate Exterior Wall with R-10 Insulation
Insulate Interior with R-6 Thermax Insulation
Double Sill Seal & Top Plates Installed
Insulated Access Door into Crawlspace incl window well
Provide and Install Support Posts down center where home halves meet
Provide and Install up to 24" height of ground break

* Travel to _____

Add: _____

* Materials are the property of Factory Home Center

Options Available At Additional Costs:

Sheetrock Interior on Crawlspace
Covers & Ladders in Window Well
Labor to install Poly in Crawlspace
Concrete Floor
Poly over exterior insulation
Steps by Exits
Rockface Block
Additional Doors / Windows
Electric Hookups
Excavation, Dirt Work, Digging, Backfilling, Radon Rock, Drain Tile & Final Landscaping

WINTER FEES EFFECTIVE SOMETIME LATE FALL!

* Prices Subject to Change*